

K M D

K A P L A N M c L A U G H L I N D I A Z , I N C .

1011 WESTERN AVE, SUITE 1011 SEATTLE, WA 98104 PHONE: 206/467-1004 FAX: 206/467-1023

ADDENDUM K

To the Contract Documents for

**BIOLOGICAL AND COMPUTATIONAL SCIENCES FACILITY
Richland, Washington**

PACKAGE 3 - FINAL REVIEW SET

September 22, 2008

This ADDENDUM modifies the original PROJECT MANUAL and DRAWINGS; dated September 16, 2008 as described below. The following sheets are to be issued with the following revisions:

PROJECT MANUAL

DRAWINGS

1. Sheet S1.05 Typical steel Framing Details
 - a. Revised size of framing studs to 6" x 18 ga. See detail 3, note 7.
2. Sheet S2.11 Foundation Plan – Level 1 – BSF North
 - a. Revised layout of interior masonry partitions at Staging and Receiving 1254.
 - b. Revised layout of interior masonry partitions at Plumbing Room 1223.
3. Sheet S2.12 Foundation Plan – Level 1 – BSF South
 - a. Revised interior masonry partitions at Energy Plant 1224, and Electrical Rooms 1220 and 1222.
 - b. Eliminated utility trench at Shelled Space 1206.
 - c. Eliminated HSS post at B9.6/BF.
4. Sheet S2.13 Foundation Plan – Level 1 – CSF
 - a. Eliminated HSS post at C1.4/CH.6.

5. Sheet S2.21 Framing Plan – Level 2 – BSF North
 - a. Revised location of depressed slab area to coordinate with Soil Microbiology Growth Chamber location across from Soils Microbiology Lab 2245, north B3.
6. Sheet S2.22 Framing Plan – Level 2 – BSF South
 - a. Eliminated HSS post at B9.6/BF.
 - b. Eliminated HSS post at B10.2/BC at Level 2.
7. Sheet S2.23 Framing Plan – Level 2 – CSF
 - a. Eliminated HSS post at C1.4/CH.6.
8. Sheet S2.31 Framing Plan – Roof – BSF North
 - a. Revised framing around roof hatch at B1.8. (Note: Revision previously noted on structural steel submittal.)
9. Sheet S2.33 Framing Plan – Roof – CSF
 - a. Revised framing for openings associated with rooftop mechanical units, RTU-4 and RTU-5.
 - b. Revised framing around roof hatch north of C5.
10. Sheet S5.02 Foundation Details
 - a. Removed detail 8.
11. Sheet S6.03 Steel Details
 - a. Revised detail 12 to coordinate with attachment of NOVUM trellis structure.
12. Sheet S9.01 Exterior Elevations
 - a. Revised various detail references on elevations 1, 2 and 3.
 - b. Removed HSS at B10 on Elevation 2 (EAST BSF).
 - c. Extent of pipe stubs at Level 2 revised from B10 to B7 on Elevation 2 (EAST BSF).
 - d. Pipe stubs at Level 2 removed at Level 2 from X to BG on Elevation 3 (NORTH BSF).
 - e. Removed full height HSS at NORTH CSF elevation beyond on Elevation 3 (NORTH BSF).
13. Sheet S9.02 Exterior Elevations
 - a. Pipe stubs at Level 2 removed at Level 2 from X to BG on Elevation 1 (WEST BSF).
 - b. Removed full height HSS at B9.6 on WEST BSF on Elevation 1 (WEST BSF).
 - c. Removed full height HSS at C1.4 on WEST CSF on Elevation 2 (WEST CSF).

- d. Pipe stubs at Level 2 removed at Level 2 from C2 to C5 on Elevation 2 (WEST CSF).
 - e. Pipe stubs at Level 2 removed at Level 2 from CG.6 to CE on Elevation 3 (SOUTH CSF).
14. Sheet S9.03 Exterior Elevations
- a. Removed HSS at east end of CSF at Level 2 near CC on Elevation 1 (NORTH CSF).
 - b. Removed HSS at CH.6 on Elevation 1 (NORTH CSF).
 - c. Removed HSS at BF on Elevation 2 (SOUTH BSF).
15. Sheet S9.07 Exterior Stud Framing Details
- a. Removed pipe stub at Level 2 on Detail 7A.
 - b. Removed pipe stub at Level 2 on Detail 9A.
 - c. Removed shelf angle on Details 9A and 9B.
 - d. Removed pipe stub at Level 2 on detail 10.
 - e. Removed details 11 through 14.
 - f. Added detail 15 showing post installed pipe stub at Level 1.
 - g. Revised detail 18 at locations of pipe stubs occurring at Level 2/Low Roof interface.

END OF ADDENDUM K